1 Cleaning/inspection MPI/dye check

2 Premaching of seating area and O-ring grooves

3 MIG welding St.St. O-ring grooves/base layer Plasma welding seating layer Stellite/ hardfacing

4 Final machining by CNC

5 Reconditioned seats after final inspection

RECONDITIONING PROCEDURE EXHAUST VALVE SEAT